BID TABULATION

Item Description: Replace Balance Tank and Valve at Civic Center Pool

Date: 11/21/2016

Budget Amount: | Budget Balance Amount:

	Capri Pools Edwardsville, IL	417 Pool Ozark,Mo.	West Port Pools Maryland Heights, Mo.			
	$39,436.00	No Bid	$31,892.00			

Capri Pools & Aquatics

22 Gateway Commerce Center Drive W
Suite 110
Edwardsville, IL 62025

October 26, 2016
Revised November 16, 2016

West Plains Civic Center
Emily Gibson
110 St. Louis Street
West Plains, MO 65775

Thank you for the opportunity to propose on your project. We believe Capri Pools & Aquatics has the necessary resources and expertise to assist you on this project.

Capri Pools' proposal is based upon the information and walk through on September 28, 2016.

Inclusions in Base Bid to remove and replace the existing balance tank.

1. Remove existing balance tank.
2. Haul off all material.
3. Provide and install new Neptune Benson fiberglass balance tank, including one (1) new valve and flanges.
4. Lower tank with pulley system through access hole in floor.
5. Connect to existing plumbing and vent lines.
6. Provide all clean up associated with this scope of work.
7. Capri Pools assumes one mobilization for the work.

Base bid to complete this work: $40,607.00. Replacement of balance tank.
Base bid to complete this work with Steel tank $39,436.00.

Option1: Installation of a new pump and motor:

1. Remove existing pump, motor, influent and effluent valves and hair/lint pot.
2. Provide and install a 15 H.P Aurora pump, motor and hair and lint pot.
3. Haul off all material.
4. Connect to existing plumbing lines.
5. Install new influent and effluent valves, flanges, vacuum and suction gauges.
6. Connect the new pump motor to the existing electrical wiring.
7. Provide owner start up and training along with pump maintenance and warranty information.

Please add $16,324.00 to the base bid. This price reflects being on site to replace the balance tank at the same time.

WESTPORT POOLS

156 Weldon Parkway
Maryland Heights, MO 63043

Office: 314-432-1801 WWW.WESTPORTPOOLS.COM Fax: 314-432-0059

Proposal Submitted To:
West Plains Civic Center
110 St Louis St, West Plains, MO 65775

Date: November 14, 2016

We hereby submit specifications and estimates for:

Balance tank replacement:

Remove existing Neptune Benson balance tank from West Plains Civic Center equipment room and relocate outdoors for disposal. Provide and install new Neptune Benson Fiberglass Balance Tank to match existing plumbing.

We propose hereby to furnish labor and material in accordance with the above specifications as described for the sum of: **$32,374.00**

Options: Includes prevailing wage

1. Construct new balance tank out of steel like existing. **Deduct $2,058.00** from base bid
2. Replace the ~~three~~ one butterfly valves associated with the balance tank. ~~ADD $2,056.00~~ ADD $1,576.00

Exclusions:

- bid bonds
- permits
- engineered drawings
- disposal of old balance tank from site
- draining/filling of pool

Total $ 31,892.00

Westport Pools has no duties or obligations beyond those contained in this proposal, and we are not bound by any terms or conditions not contained in this proposal, unless set forth in a subcontract agreement acceptable to us and signed by us. If we are directed to proceed with our work and no subcontract agreement is signed by us, the only terms and conditions governing our work are those contained in this proposal.

NOTICE TO OWNER

Failure of this Contractor to pay those persons supplying material or services to complete this contract can result in the filing of a mechanic's lien on the property, which is the subject of this agreement pursuant to Chapter 429.rsmo. To avoid this result, you may ask this Contractor for "Lien Waivers" from all persons supplying material or services for the work described in this contract. Failure to secure Lien Waivers may result in your paying for labor and material twice.